

OF JUG FILLER SPECIFICATIONS

STANDARD PEDESTAL	One piece weld construction with MDF standard 3/16" wall thickness.
OR STAINLESS STEEL PEDESTAL	One piece weld construction with MDF standard 304 schedule 10 stainless steel.
PUSH BAR	304 stainless steel with circumference exceeding 8.6". Mushroom style push bar overlaps and prevents sand and other objects from sticking push bar in the ON position. Stainless steel bubbler housing standard.
CONTROL VALVE	Requires less than 5 lbs to operate. Non-cartridge O-ring valve delivers steady stream of water. No adjustment necessary. This valve design is to operate and function at 30 to 80 PSI. Ideal operating pressure is 60 PSI.
INSTALLATION	Surface Mount installation, is designed to be anchored on top of an existing surface (concrete, etc.) with anchor bolts through a mounting plate that is welded to the unit. Surface mount carrier recommended for all surface mount installations. Flush all new or existing supply lines prior to installation. 10" bury in ground for Direct Bury models. All direct bury models have an attached valve box with bolted cover included.
FINISH	Oven baked powder coat. Choice of colors are:
WINTERIZATION	Shut off water and drain down. Remove valve during winter months.
WARRANTY	One year warranty, labor not included.
SHIPPING WEIGHT	Model 125 SM 51 lbs. Model 125 SMSS 51 lbs. Model WMSSJF 20 lbs.

MOST DEPENDABLE FOUNTAINS, INC.[™] (800) 552-6331 • (901) 867-0039 • Fax (901) 867-4008

5705 COMMANDER DR. • ARLINGTON, TN 38002-0587 www.mostdependable.com